



ADDENDUM NO. 2

DATE: JULY 7, 2020

TO: ALL PLAN HOLDERS AND PERSPECTIVE BIDDERS

FROM: ELISSA PETTIS, STAFF ENGINEER, DEWBERRY

CC: CLIFFORD KNAUER, P.E., DEWBERRY
CHRIS LIGHTFOOT, SENIOR INSPECTOR, DEWBERRY
CHRIS MITCHELL, GRANT ADMINISTRATOR, CITY OF DEFUNIAK SPRINGS

PROJECT NAME: SRF WASTEWATER IMPROVEMENTS PHASE IIA

PROJECT NUMBER: 50101203

Please note the following clarifications, corrections or supplemental information regarding the above-referenced project:

1. Pre-Bid Meeting Agenda is attached here.

Note: Please fax or email a notice of receipt back to 866-557-0076 or dlittle@dewberry.com. Please also include a copy of the signed addendum in the Bid Package. Any bidders that fail to submit a signed copy of this addendum will have their bids rejected by the City of DeFuniak Springs.

RECEIPT OF ADDENDUM

ACCEPTED BY:

Signature of Bidder

Date

TYPE OR PRINT NAME OF BIDDER

PRE-BID MEETING AGENDA

CITY OF DEFUNIAK SPRINGS – SRF WASTEWATER IMPROVEMENTS PH. IIA

PROJ. NUMBER: 50101203 DATE: JULY 8TH, 2020 TIME: 2:00pm (CST)

1. PROJECT DESCRIPTION

This project includes the installation of one proposed lift stations adjacent to I-10 and one 12-inch force main from U.S. Hwy 331 at the intersection of I-10 to the City's wastewater treatment facility. Construction quantities include approximately 14,500 -ft of 12-inch forcemain and 3,600-ft of 14-inch directional bore, and one 10-ft dia and 20-ft deep lift station rated at 800 gpm.

The wastewater lift stations consist of the following:

- I-10 Lift Station: One 800 gpm @ 165-ft TDH duplex station with a package automatic back up diesel engine bypass pump and a diesel generator system and a ten foot diameter, twenty foot deep HDPE lined precast concrete wetwell.

The Project Alternates consist of the following:

- Approximately 1,200-ft of 8-inch forcemain and replacement of stormwater drainage structures impacted by the forcemain installation.
- Upsizing the proposed 12-inch PVC / 14-inch HDPE forcemain from Bruce Ave to the WWTF to a 14-inch PVC / 16-inch HDPE forcemain.
- Substitution of HDPE directional bore pipe with Fusible PVC pipe for base bid and alternates

2. DISCUSSION ITEMS:

- Visit and inspect site(s)
- 5% bid bond
- Railroad insurance requirements
- Project schedule
- SRF Funded Project
 - i. FDEP Supplementary Conditions
 - ii. Davis Bacon Wage Rates / Certified Payrolls
 - iii. American Iron and Steel Requirements
- Qualification package – appendix E
- Lift station electrical
- Lump sum contract
- Alternates
- Permits
- Utility conflicts and proximity to residents

3. IMPORTANT BID DATES:

All questions must be submitted in writing by Thursday July 9th, 2020 @ 5:00 p.m. (CST)

Bids are due and will be opened on Thursday, July 23rd, 2020 @ 2:00 p.m. (CST)

Anticipated notice to proceed: August 24th, 2020. Substantial completion 270 days; final completion 60 days

PRE-BID MEETING AGENDA

CITY OF DEFUNIAK SPRINGS - SRF WASTEWATER IMPROVEMENTS PH. IIA

***** Go Over Bid Schedule*****

OPEN THE FLOOR TO ANY QUESTIONS

PRE-BID MEETING AGENDA

CITY OF DEFUNIAK SPRINGS - SRF WASTEWATER IMPROVEMENTS PH. IIA